

**PELANGAN GOLD PROSPECT - WEST LOMBOK PROJECT
PHASE 2 DRILLING
DIAMOND DRILL HOLE STATISTICS**

HOLE ID	Prospect	COORDINATE		EL. (m above MSL)	AZIMUTH (N...°E)	INCL (...°)	STARTED	FINAL LENGTH (m)	SIGNIFICANT INTERSECTION					
		UTM							Comments	FROM	TO	Interval	Au (g/t)	Ag (t/t)
		E	N											
PLD003	Raja	384530.9	9028672.1	120.4	65	-65	27/03/2011	300.30	including and	232.95 237.50 240.70	249.50 245.20 245.20	16.55 7.7 4.5	5.5 10.9 17.6	3.7 6.1 8
PLD004	Raja	384656.2	9028587.2	186.8	70	-50	27/03/2011	150.00	including	79.25 88.70	90.20 90.20	10.95 1.5	2 5.6	34 166
PLD005	Raja	384463.8	9028885.9	71.6	100	-50	29/03/2011	149.20		72.20 92.90	73.95 94.85	17.5 1.95	1.15 1.16	4.9 13.7
PLD006	Raja	384656.2	9028587.2	186.8	70	-68	01/04/2011	149.00	including	110.05 110.05	126.20 112.50	16.15 2.45	1.4 4.7	12 34
PLD007	Raja	384490.0	9028777.6	77.6	62	-45	11/04/2011	158.75	including including	78.80 78.80 88.10 127.70	118.50 96.20 94.25 128.45	39.7 17.4 6.15 0.75	9.4 19.4 37.7 22.1	15.7 28.3 26 15.4
PLD008	Raja	384615.3	9028682.7	161.2	75	-45	15/04/2011	156.00	including including	70.35 70.35 93.70 100.20	81.90 73.85 105.50 102.20	11.55 3.5 11.8 2	9.8 26.1 1.4 3.7	31.1 96.5 9.2 22.6
PLD009	Raja	384530.9	9028672.1	120.4	32	-60	13/04/2011	295.00	including	217.30 217.30	225.50 221.60	8.2 4.3	4.4 7.5	3.66 3.9
PLD010	Raja	384615.3	9028682.7	161.2	72	-70	24/04/2011	195.00	including and	127.35 140.40 140.80	149.40 149.40 142.20	22.05 9 1.4	2.7 4.6 11.5	2.8 1.6 2.3
PLD011	Raja	384529.0	9028670.0	117.0	65	-60	28/04/2011	282.35	including	210.20 211.50	226.70 216.25	16.5 4.75	3.2 8.2	16.4 41.9
PLD012	Raja	384490.0	9028777.6	77.6	55	-70	01/05/2011	310.10		108.80	111.60	2.8	0.5	5.4

										188.50	194.50	6	0.5	2
PLD013	Raja	384631.4	9028649.5	184.3	82	-65	07/05/2011	201.00		110.40	134.90	24.5	1.3	5.9
									including	117.80	126.75	8.95	2.3	11.2
PLD014	Raja	384711.1	9028441.1	191.7	50	-65	31/05/2011	159.00		74.60	111.80	37.2	2.5	14.2
									including	90.70	99.90	9.2	4.1	24
PLD015	Raja	384591.5	9028646.3	168.1	84.6	-70	02/06/2011	341.50	No Significant Result					
PLD016	Raja	384566.9	9028767.9	106.6	63	-70	06/06/2011	157.90		91.90	102.90	11	2.17	8.6
									including	93.95	96.25	2.3	4	14.5
									and	98.50	99.20	0.7	4.5	4
PLD017	Raja	384709.1	9028440.0	191.6	15	-65	09/06/2011	195.35		132.40	138.40	6	2.2	13.1
									including	132.40	133.70	1.3	4.9	10.5
PLD018	Raja	384388.5	9029050.0	69.9	65	-47	21/06/2011	162.90		79.30	80.00	0.70	2.4	2.7
PLD019	Raja	384663.3	9028360.5	221.6	70	-46	22/06/2011	228.10		147.10	152.30	5.2m	4.1	10.3
									including	147.70	148.45	0.75	14	43.7
									and	151.75	152.30	0.55	14.5	5.2
										160.80	174.75	13.95	2.7	19.9
									including	160.80	163.20	2.4	7.1	34.8
									and	173.75	174.75	1	4.7	40.9
PLD020	Tanjung	384309.8	9028698.1	183.9	215	-50	17/06/2011	187.00		66.95	68.00	1.05	1.3	1.5
										78.65	80.35	1.7	2.5	0.8
										110.05	111.00	0.95	1.4	3.3
PLD021	Raja	384640.2	9028566.2	171.1	65	-70	25/06/2011	296.70	No Significant Result					
PLD022	Raja	384783.9	9028193.0	269.9	80	-55	28/06/2011	182.20		101.80	117.60	15.8	3.6	19.7
									including	111.40	117.00	5.6	7	12.6
									including	115.60	117.00	1.4	18.2	10.9
PLD023	Tanjung	384245.7	9028742.7	183.1	210	-50	02/07/2011	164.25	No Significant Result					
PLD024	Raja	384663.3	9028360.5	221.6	65	-67	08/07/2011	280.45		223.85	225.80	1.95	3.3	6.4
PLD025	Raja	384783.1	9028193.0	271.1	44	-65	11/07/2011	214.35		145.55	160.55	15	1	25.7
										165.30	175.35	10.05	1.1	1.2
										189.80	191.10	1.3	4.1	2.3
PLD026	Raja	384374.6	9029164.6	44.2	65	-55	10/07/2011	77.60	Abandoned due to water					
PLD027	Tanjung	384120.8	9028807.5	190.2	210	-50	10/07/2011	247.25		167.20	193.40	26.2	4.2	3.6
									including	167.20	168.50	1.3	30.1	12.3
									including	189.15	192.60	3.45	12.3	13
PLD028	Raja	384375.2	9028828.0	121.1	70	-61	15/07/2011	334.20		251.05	252.40	1.35	1	6.2
PLD029	Raja	384313.1	9029257.0	53.3	65	-50	16/07/2011	154.15	No Significant Result					

PLD030	Raja	384158.7	9029448.0	32.4	65	-50	24/07/2011	154.20	No Significant Result					
PLD031	Raja	384728.4	9028268.0	266.1	70	-50	26/07/2011	213.15	including	154.70	158.60	3.9	3.86	14.2
										156.10	157.25	1.15	9.82	20.2
PLD032	Raja	384809.5	9028103.0	267.3	65	-45	27/07/2011	191.40	including	87.20	100.35	13.15	1.4	25.8
										97.05	100.35	3.3	2.3	41.2
PLD033	Tanjung	384003.4	9028878.0	219.0	210	-50	28/07/2011	187.95		114.95	115.60	0.65	1.04	8.9
PLD034	Tanjung	383794.0	9029010.4	230.1	210	-50	03/08/2011	100.00	No Significant Result					
PLD036	Tanjung	383897.1	9028942.8	228.1	210	-50	07/08/2011	15.20	<i>Drill rig destroyed</i>					
PLD037	Raja	384809.5	9028103.0	267.3	65	-75	06/08/2011	39.45	<i>Drill rig destroyed</i>					
PLD038	Raja	384728.4	9028268.0	266.1	70	-70	07/08/2011	11.75	<i>Drill rig destroyed</i>					
Total Drilled Length:								6,642.70						

Qualified Person

The technical information in this document has been reviewed by Southern Arc's Executive Vice President, Andrew Rowe, B. App. Sc. Geology, MAusIMM. Mr. Rowe has over 18 years of international mineral exploration experience throughout Southeast and Central Asia and Australia. During this time he has held such positions as Principal Geologist – Feasibility Studies, Senior Geologist and Consulting Geologist. The technical information in this document has also been reviewed by Southern Arc's President & Chief Operating Officer, Dr. Mike Andrews, PhD, FAusIMM, who has sufficient experience relevant to the style of mineralization under consideration and qualifies as a Qualified Person as defined by National Instrument 43-101.

The drill program and sampling protocol is managed by Southern Arc under the supervision of Andrew Rowe. The diamond drill holes are drilled at PQ, HQ and NQ sizes depending on hole depth and core recovery to date has averaged 98.0%. Half core is cut by rock saw and is generally sampled using nominal 1-metre intervals; however, sample intervals are varied according to geological contacts and have ranged between 0.2 to 2.5 metres in length. Three quality control samples (one blank and two standards) are inserted into each batch of 40 samples. The half core samples are securely transported from the project site to the Intertek Testing Services ("ITS") sample preparation laboratory in Sumbawa Besar via private truck hired by Southern Arc. Sample pulps are then sent to the ITS Jakarta laboratory by ITS. Gold is analysed by fire assay with AAS finish and a four-acid digestion with ICP-MS finish is used to analyse a full suite of elements including silver and base metals. ITS is one of the world's largest product and commodity testing, inspection and certification organizations. The Jakarta laboratory is ISO 17025 accredited and employs a Laboratory Information Management System for sample tracking, quality control and reporting.



**MENCANGGAH EPITHERMAL DISTRICT
PHASE 1 DRILLING
DIAMOND DRILL HOLE STATISTICS**

HOLE ID	Prospect	COORDINATE		EL. (m above MSL)	AZIMUTH (N...°E)	INCL (...°)	STARTED	FINAL LENGTH (m)	SIGNIFICANT INTERSECTION						
		UTM							Comments	FROM	TO	Interval	Au (g/t)	Ag (t/t)	
		E	N												
MCG001	Waterfall	388177.0	9022741.0	277.0	210	-50	24/07/2011	288.30	including	257.50	259.80	2.30	3.96	176.7	
MCG002	Waterfall	388026.6	9022819.6	309.4	210	-55	02/08/2011	138.30	including	259.00	259.80	0.80	7.55	412.0	
MCG003	Waterfall	387905.0	9022620.6	304.6	30	-50	12/10/2011	316.60		118.70	120.70	2.00	5.15	10.5	
MCG004	Waterfall	387838.1	9022677.3	287.6	30	-60	12/10/2011	358.70		118.70	118.90	0.20	9.83	2.9	
MCG005	Waterfall	387980.4	9022611.3	308.9	30	-60	17/10/2011	256.80		221.90	222.20	0.30	1.60	1.0	
MCG006	Waterfall	388063.4	9022543.1	273.3	30	-50	24/10/2011	178.50		115.90	117.20	1.30	3.80	1.5	
MCG007	Waterfall	387903.4	9022618.8	304.6	210	-50	26/10/2011	190.50		74.30	75.30	1.00	1.20	2.5	
MCG008	Waterfall	388114.0	9022438.0	254.0	30	-45	28/10/2011	50.00		77.15	78.00	0.85	3.30	4.7	
MCG009	Waterfall	387836.0	9022673.6	287.6	210	-60	27/10/2011	165.00		229.00	230.00	1.00	1.40	3.3	
MCG010	Waterfall	387979.2	9022609.5	307.0	210	-70	28/10/2011	203.30		102.00	106.40	4.40	1.10	1.3	
MCG011	Waterfall	387766.3	9022714.8	256.3	210	-70	03/11/2011	149.00		122.35	123.95	1.60	11.00	2.6	
MCG012	Waterfall	387631.1	9022695.5	187.1	30	-45	07/11/2011	252.00	<i>No Significant Result</i>						
MCG013	Waterfall	388062.7	9022542.3	273.3	0	-90	04/11/2011	226.50	<i>Hole abandoned at 50 m due to collapse</i>						
MCG014	Waterfall	388116.2	9022445.3	237.4	30	-50	04/11/2011	275.90		84.10	85.50	1.40	2.40	3.1	
MCG015	Waterfall	387758.2	9022556.0	258.5	30	-55	08/11/2011	400.80		95.90	96.20	0.30	3.40	22.0	
										98.40	98.70	0.30	1.50	2.5	
										112.40	112.80	0.40	2.10	4.4	
										111.05	112.00	0.95	1.50	9.2	
										118.85	119.60	0.75	3.00	10.8	
										131.90	132.90	1.00	1.70	7.0	
										169.85	170.85	1.00	1.01	2.0	
										41.00	41.80	0.80	1.46	6.1	
										<i>No Significant Result</i>					
										<i>No Significant Result</i>					
										125.85	126.35	0.50	1.3	7.9	
										260.90	261.70	0.80	1.17	2.4	
										265.70	268.35	2.65	1.03	4.7	
										16.00	18.00	2.00	1.78	1.3	

										48.55	49.60	1.05	1.49	4.5
										313.00	313.70	0.70	1.23	4.1
										363.00	363.95	0.95	1.42	10.4
MCG016	Waterfall	387689.0	9022601.0	248.9	30	-50	10/11/2011	393.30		160.15	161.00	0.85	1.35	3.8
									including	168.50	173.25	4.75	15.59	15.1
										170.20	170.95	0.75	79.00	20.3
										179.55	180.40	0.85	1.08	7.1
										182.40	183.45	1.05	1.96	8.8
										184.90	185.50	0.60	1.75	6.8
										188.45	189.20	0.75	1.72	25.6
										209.30	210.20	0.90	2.17	19.4
										371.10	373.35	2.25	0.99	7.6
MCG017	Waterfall	388060.8	9022539.1	273.3	210	-70	12/11/2011	264.10		79.20	79.60	0.40	1.76	34.2
MCG018	Waterfall	387762.0	9022726.0	260.0	30	-50	12/11/2011	236.45	No Significant Result					
MCG019	Waterfall	387555.0	9022767.0	170.6	30	-50	19/11/2011	196.50	No Significant Result					
MCG020	Waterfall	388211.4	9022415.8	209.5	30	-50	20/11/2011	327.00		122.60	124.50	1.90	1.46	6.5
										150.90	151.90	1.00	1.91	4.4
MCG021	Waterfall	388265.4	9022369.7	217.8	30	-50	24/11/2011	195.6		98.00	100.00	2.00	2.38	35.6
MCG022	Waterfall	388367.4	9022291.5	141.8	70	-60	24/11/2011	292.0	No Significant Result					
MCG023	Waterfall	388286.8	9022633.1	260.0	15	-50	23/11/2011	312.80	No Significant Result					
MCG024	Waterfall	387481.8	9022793.7	129.4	30	-50	24/11/2011	259.50		215.60	217.60	2.00	1.66	4.8
										224.90	228.70	3.80	1.00	4.1
MCG025	Waterfall	387820.0	9022436.5	274.3	250	-55	25/11/2011	225.00	No Significant Result					
MCG026	Waterfall	388356.2	9022650.6	253.3	30	-50	29/11/2011	241.40		107.90	109.40	1.50	1.10	7.0
MCG027	Waterfall	388517.1	9022427.0	164.1	30	-50	03/12/2011	240.10	No Significant Result					
MCG028	Bising	388254.7	9023900.8	388.5	195	-50	05/12/2011	326.50		35.60	86.85	51.25	1.50	1.4
									Including	38.90	39.20	0.30	2.80	0.9
									and	47.90	52.00	4.10	2.30	0.9
									and	53.40	58.45	5.05	3.50	1.1
									Including	56.40	57.40	1.00	11.00	1
									and	60.15	63.90	3.75	4.90	0.7
									Including	61.75	62.05	0.30	40.30	0.6
									and	65.60	76.40	10.80	1.50	2.8
									Including	75.95	76.40	0.45	13.40	29.4
MCG029	Bising	388069.3	9023936.1	434.7	195	-50	08/12/2011	234.00		40.10	83.00	42.90	0.40	2.3
									Including	47.10	47.70	0.60	3.50	0.9
									and	74.60	75.00	0.40	2.90	26
									and	80.00	81.00	1.00	1.00	4
MCG030	Bising	388157.1	9023887.5	421.6	195	-50	07/12/2011	201.50		34.00	73.00	39.00	1.80	3.1
									Including	38.60	40.00	1.40	1.10	1

									and	46.50	50.10	3.60	1.70	2
									and	56.30	66.00	9.70	4.90	5.9
									Including	59.20	59.50	0.30	89.00	27.6
									and	71.00	73.00	2.00	1.10	5
MCG031	Bising	388331.2	9023866.8	367.8	195	-50	08/12/2011	283.90	Including	34.60	100.00	65.40	0.52	1.4
									and	36.95	37.60	0.65	6.50	2.2
									Including	74.20	78.60	4.40	2.10	7.3
									and	74.20	75.10	0.90	6.80	27.8
									Including	156.75	157.50	0.75	47.70	13.2
MCG032	Bising	388564.1	9023738.9	329.6	195	-50	11/12/2011	250.00	Including	11.70	49.00	37.30	1	1.4
									and	19.00	20.00	1.00	5.71	0.6
									Including	25.20	30.00	4.80	4	2.5
									and	29.00	30.00	1.00	13.5	8.9
									Including	145.60	152.60	7.00	0.3	1.6
									and	190.10	198.20	8.10	0.4	1.8
MCG033	Bising	388217.9	9024024.9	407.3	230	-50	11/12/2011	387.20	Including	134.10	170.55	36.45	0.3	1.5
									and	150.80	170.55	19.75	0.4	2
									Including	214.15	224.45	10.30	0.3	1.1
									and	220.35	220.70	0.35	1.7	6.5
									Including	258.55	261.10	2.55	0.4	0.5
									and	259.10	259.55	0.45	1.4	1.6
MCG034	Bising	388376.4	9023676.5	358.0	230	-50	13/12/2011	304.50	Including	8.20	15.90	7.70	0.5	5.1
									and	10.20	11.60	1.40	1.2	23.2
									Including	46.50	55.10	8.60	0.4	4.2
									and	151.00	152.70	1.70	0.4	2.1
									Including	169.70	170.50	0.80	0.9	2.7
									and	182.50	185.70	3.20	0.6	2.7
									Including	286.70	288.10	1.40	0.2	8.6
MCG035	Bising	388255.2	9023500.4	351.3	230	-50	16/12/2011	298.10	Including	29.00	48.45	19.45	0.2	0.9
									and	63.35	72.50	9.15	0.7	0.6
									Including	65.00	66.40	1.40	1.7	0.9
									and	150.90	154.30	3.40	0.4	2
									Including	163.15	166.50	3.35	0.5	1.4
									and	176.65	177.30	0.65	2.5	1.4
Total Drilled Length:										8,919.65				

Qualified Person

The technical information in this document has been reviewed by Southern Arc's Executive Vice President, Andrew Rowe, B. App. Sc. Geology, MAusIMM. Mr. Rowe has over 18 years of international mineral exploration experience throughout Southeast and Central Asia and Australia. During this time he has held such positions as Principal Geologist – Feasibility Studies, Senior Geologist and Consulting Geologist. The technical information in this document has also been reviewed by Southern Arc's President & Chief Operating Officer, Dr. Mike Andrews, PhD, FAusIMM, who has sufficient experience relevant to the style of mineralization under consideration and qualifies as a Qualified Person as defined by National Instrument 43-101.

The drill program and sampling protocol is managed by Southern Arc under the supervision of Andrew Rowe. The diamond drill holes are drilled at PQ, HQ and NQ sizes depending on hole depth and core recovery to date has averaged 98.0%. Half core is cut by rock saw and is generally sampled using nominal 1-metre intervals; however, sample intervals are varied according to geological contacts and have ranged between 0.2 to 2.5 metres in length. Three quality control samples (one blank and two standards) are inserted into each batch of 40 samples. The half core samples are securely transported from the project site to the Intertek Testing Services ("ITS") sample preparation laboratory in Sumbawa Besar via private truck hired by Southern Arc. Sample pulps are then sent to the ITS Jakarta laboratory by ITS. Gold is analysed by fire assay with AAS finish and a four-acid digestion with ICP-MS finish is used to analyse a full suite of elements including silver and base metals. ITS is one of the world's largest product and commodity testing, inspection and certification organizations. The Jakarta laboratory is ISO 17025 accredited and employs a Laboratory Information Management System for sample tracking, quality control and reporting.



**SELODONG GOLD PROSPECT - WEST LOMBOK PROJECT
PHASE 2 DRILLING
DIAMOND DRILL HOLE STATISTICS**

HOLE ID	Prospect	COORDINATE		EL. (m above MSL)	AZIMUTH (N...°E)	INCL (...°)	STARTED	FINAL LENGTH (m)	SIGNIFICANT INTERSECTION					
		UTM							Comments	FROM	TO	Interval	CU (%)	AU (g/t)
		E	N											
SLD031	Selodong	389442.5	9021771.0	184.7	270	-50	31/12/2011	603.30		285	368	83.0	0.08	0.33
Total Drilled Length:								603.30						

Qualified Person

The technical information in this document has been reviewed by Southern Arc's Executive Vice President, Andrew Rowe, B. App. Sc. Geology, MAusIMM. Mr. Rowe has over 18 years of international mineral exploration experience throughout Southeast and Central Asia and Australia. During this time he has held such positions as Principal Geologist – Feasibility Studies, Senior Geologist and Consulting Geologist. The technical information in this document has also been reviewed by Southern Arc's President & Chief Operating Officer, Dr. Mike Andrews, PhD, FAusIMM, who has sufficient experience relevant to the style of mineralization under consideration and qualifies as a Qualified Person as defined by National Instrument 43-101.

The drill program and sampling protocol is managed by Southern Arc under the supervision of Andrew Rowe. The diamond drill holes are drilled at PQ, HQ and NQ sizes depending on hole depth and core recovery to date has averaged 98.0%. Half core is cut by rock saw and is generally sampled using nominal 1-metre intervals; however, sample intervals are varied according to geological contacts and have ranged between 0.2 to 2.5 metres in length. Three quality control samples (one blank and two standards) are inserted into each batch of 40 samples. The half core samples are securely transported from the project site to the Intertek Testing Services ("ITS") sample preparation laboratory in Sumbawa Besar via private truck hired by Southern Arc. Sample pulps are then sent to the ITS Jakarta laboratory by ITS. Gold is analysed by fire assay with AAS finish and a four-acid digestion with ICP-MS finish is used to analyse a full suite of elements including silver and base metals. ITS is one of the world's largest product and commodity testing, inspection and certification organizations. The Jakarta laboratory is ISO 17025 accredited and employs a Laboratory Information Management System for sample tracking, quality control and reporting.